

IPLEX BLUELINE FLOW CHART @ 12.8°C

POISEUILLE FORMULA (R<2000)

$$Q = \frac{d^4}{5037}$$

$$V = 0.25276 \frac{d^2}{i}$$

$$i = \frac{5037 Q}{d^4}$$

LAMONT FORMULA S3 (3000<R<300000)

$$Q = \frac{2304}{d^{2.6935} i^{0.5645}}$$


$$V = 0.55254 \frac{d^{0.6935}}{i^{0.5645}}$$

$$i = \frac{905032 Q^{1.772}}{d^{4.772}}$$

Explanation of Units

- R = Reynolds No.
- Q = Flow rate (Litres per second)
- i = Hydraulic Gradient
- V = Flow Velocity (metres per second)
- d = Mean Pipe Internal Diameter (mm)

NOTE: This chart should be used as a guide only. All designs should be checked from first principles, based upon the above equations.





BLUELINE PN12.5 FLOW CHART



Iplex Pipelines NZ Limited PE Product Range

GREENLINE

REDLINE™

BLUELINE & POLIPEX™

BLACKLINE

RURAL BLACK

PLASSON®

ALKATHENE™

NOVATUBE

NEXUS™

NOVAFLO™

EFFLUENT PIPE

FARMTUFF™

NEXUS™ CULVERT

© 2018 IPLEX PIPELINES (NZ) LIMITED. NEXUS™, IPLEX™, NOVAFLO™, NOVATHENE™, FARMTUFF™, REDLINE™ are registered trademarks of IPLEX PIPELINES (NZ) LIMITED. The information contained in this brochure is intended to be of a general nature and should be used as a guide only. Before relying on any of the information in this brochure, you should first refer to the appropriate codes and standards and consult Iplex Pipelines and/or your local authorities.

Version 2

This version supersedes all previous versions or editions of this flow chart.

Iplex Pipelines NZ Limited.

Call Centre - Phone: 0800 800 262 Fax: 0800 800 804
Web site - www.iplex.co.nz

Offices At:

Auckland: PO Box 13772 Onehunga, Level 1, 64 Cook St, Auckland Central.
Palmerston North: Private Bag 11019, 67 Malden Street.
Christchurch: PO Box 16225, 22 Braeburn Drive, Sockburn.

